

**AMENDMENT NO. 1 APRIL 2008
TO
IS 13917 : 2003 STRANDED WIRE ROPES FOR
MINE HOISTING — TECHNICAL DELIVERY
REQUIREMENTS**

(First Revision)

(Page 1, clause 4.1.1.2, first sentence) — Substitute the following for the existing:

'The actual rope diameter measured on the newly completed rope in the unloaded state shall be within +4 percent of the nominal diameter.'

-1
(ME 10)

Reprography Unit, BIS, New Delhi, India