

**AMENDMENT NO. 2 SEPTEMBER 2005
TO**

**IS 11809 : 1994 LINING FOR CANALS BY STONE
MASONRY — CODE OF PRACTICE**

(First Revision)

(Page 1, clause 2.1) — Substitute the following for the existing clause:

2.1 The following standards contain provisions which through reference in this text, constitute provisions of this standard. At the time of publication, the editions indicated were valid. All standards are subject to revision, and parties to agreements based on this standard are encouraged to investigate the possibility of applying the most recent editions of the standards indicated below:

<i>Sl No.</i>	<i>Title</i>
IS 1122 : 1974	Method of test for determination of true specific gravity of natural building stones (<i>first revision</i>)
IS 1126 : 1974	Method of test for determination of durability of natural building stones (<i>first revision</i>)
IS 3873 : 1993	Laying cement concrete/stone slab lining on canals — Code of practice (<i>second revision</i>)
IS 4558 : 1983	Code of practice for under-drainage of lined canals (<i>second revision</i>)

(Page 1, clause 4.1, line 4) — Substitute 'loss of weight should not be more than 10 percent when tested according to IS 1126' for 'and soundness not less than 10 % loss of weight after 5 cycles when tested according to IS 1126 : 1974'.

(Page 1, clause 4.2) — Substitute the following for the existing clause:

4.2 The stone should be laid on 1 : 2 lime mortar (1 lime : 2 sand) or 1 : 3 cement mortar (1 cement : 3 sand) over a bed of minimum 12 mm thick lime/cement mortar. Masonry mortar shall conform to IS 2250 . The joints shall be pointed with same mortar.

Amend No. 2 to IS 10809 : 1994

(*Page 1, clause 4.5*) — Add the following at the end of the clause:

‘Concrete ribs should be made by using Portland pozzolana cement or incorporation of flyash as replacement material of ordinary Portland cement up to 35 percent by weight, in the concrete mix.’

(*Page 1, clause 4.10*) — Insert the following clause after this clause:

‘**4.11** All exposed surface of masonry shall be kept continuously moist for a minimum period of 21 days.’

(WRD 13)